

Laboratory Report

Date

22-April-2008

Customer PVC WINDOWS

27/8 RIVERLAND DRIVE, LOGANHOLME, BRISBANE QLD 4129

Test No:

AZT0044.08.xls



NATA Accredited Laboratory No: 15147

Azuma Design Pty Limited 160 Newton Rd Wetherill Park. NSW 2164 Ph 02 9604 0255 E-Mail info@azumadesign.com.au

TESTING LABORATORY REPORT



Reported Robert Irwin by:

Checked Nathan Olsen by:

Valley Olsen

Date : 22-Apr-08 Test No: AZT0044.08 .xls

NATA Accredited Laboratory No: 15147

Testing to AS 2047.1 as per test method 4420.0 to .6

Wind and Water Penetration Testing

Manufacturer / Customer

PVC WINDOWS

Test Sample Data

Deflection Ratio

180

Unit type	casement/fixed/casement			
Unit code	6040 series	S		
Size	H (mm)	1800		
	W (mm)	2700		
Design Pa:	950			

Tested For	Y/N	Rating	Units
Structural Deflection ?	Yes	950	Pa
Air Infiltration ?	Yes	75/150	Pa
Operating Force Initial / constant ?	No	N/A	N
Water Penetration ?	Yes	300	Pa
Ultimate Strength ?	Yes	1500	Pa

Test Unit Specifications

Results

	Sizes		н	w	Area sq m	Glass Type	Structural Framing Member	Span (mm)	Allowable Deflection	Deflection Result	Actual Ratio	Test Press (Pa)	Results
Frame		0.00	1800	2700	4.86		Interlock P	0	4	0.00			
	casement 1 8	2	1735	705	1.22		Interlock N	0		0.00			
Sash	fixed		1790	1280	2.29		Mullion P	1660	9.22	8.99	185	950	Р
		0	0	0	0.00		Mullion N	1660	9.22	8.44	185	950	Р
	Thickness (mm)	Н	W			Transom P	0		0.00			
	casement 1 &2	4-16-4	1587	562	0.89	low.E. clear float	Transom N	0		0.00			П
Glass	fixed	4-16-4	1692	1142	1.93	low.E. clear float	H/L Trans P	0		0.00			
	0	0.00	0	0	0.00	0	H/L Trans N	0		0.00			
	0	0.00	0	0	0.00	0	H/L Mullion P	0		0.00			
							H/L Mullion N	0		0.00			
							Meet Style P	0		0.00			
							Meet Style N	0		0.00			
							Spare	0	N - 1	0.00			
							Spare	0		0.00			

TESTING LABORATORY REPORT

Test equipments

The test equipment and methods used in the above test comply with the requirements of AS 4420.1-6.

Test Specimen

See drawings at the end of this report.

Test Methods

The test unit was fixed into the rig as outlined in AS 4420.1.

Deflection Test

The unit was subjected to both positive and Negative pressure as prescribed in AS 4420.2. After the initial settling in of the unit at the 50% of the required test pressure, the differential pressure was then applied

Results of Test

The test unit satisfied the requirements of AS 2047.1 in both the positive and negative deflection at the nominated design pressure.

Observations

0		10745115	ejecili i	STEEL PROPERTY.
186				

Air Infiltration Test

The test was first completely sealed against air leakage as per AS 4424.4 to determine the air leakage of the test rig. It was then subjected to 75 Pa of both positive and negative pressure, and 150 Pa of both negative and positive pressure. Differential pressures were recorded. The test unit was then unsealed and subjected to 75 Pa of both positive and negative pressure. Differential pressures were recorded and air leakage then calculated. The actual leakage of the test unit was then determined.

Barometric pi	ressure (Pbar):	1018		Air tempera	ature (°C)	20
	9	SEALED	UNSE	ALED		
Max Pressure (Pa)	Positive (Pa)	Negative (Pa)	Positive (Pa)	Negative (Pa)		
75	1	2	3	2		
150	3	3	4	4		

Took Deserves	Pressure	Building / Window leakage flow		Test results				
Test Pressure	Direction	Туре	1/s m ²	ls"+m"	s'm' Is m Pos +		Neg -	
75 Pa	+/-	Air conditioned	1.0	0.14	0.00	Passed	Passed	
75 Pa	+	Non air conditioned	5.0	0.14	0.00	Passed	N/A	
150 Pa	+/-	Air conditioned	1.6	0.05	0.05	Passed	Passed	
150 Pa	+	Non air conditioned	8.0	0.05	0.05	Passed	N/A	

TESTING LABORATORY REPORT

Results of test

The test unit satisfied the requirement of AS 2047. The test unit was tested to AS 4420.4. The net flow readings are as follows:

Observation

0		
		Till was 13 hard

Operating Force

OPERATING FORCE (N)

		Opening Force	Closing Force
Initiating Movement	Sash 1	0	0
Sustaining Movement	Sash 1	0	0
Initiating Movement	Sash 2	0	0
Sustaining Movement	Sash 2	0	0
Initiating Movement	Sash 3	0	0
Sustaining Movement	Sash 3	0	0

A force gauge was attached to the operating handle of the sash to determine the force required to set the sash in motion and thereafter to maintain motion as per AS 4420.3.

Results of test

_	 		 	 		
^						

Observations

Observations	
0	
NAME OF TAXABLE PARTY.	

TESTING LABORATORY REPORT

WATER PENETRATION

Water was applied to the exterior of the test unit with no less than 0.05 ls-1m-2 for a period of five minutes at zero pressure. After five minutes, a nominated pressure was applied for fifteen minutes as per AS 4420.5.

Maximum pressure (Pa) applied for 15 minutes (Nominated pressure)

300

Results of test

The test unit satisfied the requirement of AS 2047 in positive pressure at the nominated design pressure.

Observations

After one minute @ 450pa, water leaked from both bottom corner glazing beads of fixed sash.

ULTIMATE STRENGTH TEST


A pressure nominated on part 1 of this report and determined by AS 2047, table 2.5 was applied to the test unit for a period of 10 seconds as per AS 4420.6.


Max. pressure reached for 10 seconds			
Positive	Negative		
1500	1500		

Results of test:	Y or N
Dislodgement of any glass?	No
Dislodgement of a frame or any part of a frame?	No
Removal of alignment with or without its framing sash from a frame?	No
Loss of support of a frame such as when it is unstable in its opening in the building structure?	No
Failure of any sash, locking device, fasteners or supporting stay which would allow an opening light to come open?	No

Observations

6043 series casement window







NATA Accredited Laboratory Number: 15147

This laboratory is accredited by the National Association of Testing Authorities, Australia. The tests reported herein have been performed in accordance with its scope of accreditation. This document shall not be reproduced, except in full.

Checked by:

